
	REVISIONS																									
LTR								DES	CRIP	TION	!								DAT	E (YF	-MO-	DA)	-	PPR	OVE	, T
									-																	
REV		_										L			L					_		<u> </u>	L		L	Ш
SHEET		_									L			_	L	L	<u> </u>			L_	L	<u> </u>			L	
REV		_								_	<u> </u>				<b> </b>		ļ		L.	L	_	L	<u></u>		L	Ш
SHEET		↲													L					L		L			L	Ш
REV ST		L	RE	V			Ш									L.,			L_			L	L		L	Ш
PMIC N	/A		-	D		1 2 3 4 5 6 7 8  PREPARED BY  CHECKED BY  Thomas J. Riccourti					9 10 11 12 13 14 15 16 17  DEFENSE ELECTRONICS SUPPLY CENTER DAYTON, OHIO 45444															
THIS DE		IN ( S AV DEP	G AILA	<b>MENT</b>		APF DR	ROVI	5P. B)	PROV	AL C	LY CHE	u le	,	(	OCTA MONO SIZE	L Bl	US T HIC	RANS SILI CAGE	DIGITAL, BIPOLAR CMOS, SCEIVERS, TTL COMPATIBLE, ICON							
	TMENT							ILEV						1	A 67268 59 SHEET					1		- <del>-</del>				

DESC FORM 193 SEP 87

× U.S. GOVERNMENT PRINTING OFFICE: 1987 — 748-129/60913



- 1.1 Scope. This drawing forms a part of a one part one part number documentation system (see 6.6 herein). Two product assurance classes consisting of military high reliability (device classes B, Q, and M) and space application (device classes S and V), and a choice of case outlines and lead finishes are available and are reflected in the Part or Identifying Number (PIN). Device class M microcircuits represent non-JAN class B microcircuits in accordance with 1.2.1 of MIL-STD-883, "Provisions for the use of MIL-STD-883 in conjunction with compliant non-JAN devices". When available, a choice of radiation hardness assurance (RHA) levels are reflected in the PIN.
  - 1.2 PIN. The PIN shall be as shown in the following example:



Drawing number

- 1.2.1 Radiation hardness assurance (RHA) designator. Device classes M, B, and S RHA marked devices  $\frac{1}{2}$  meet the MIL-M-38510 specified RHA levels and shall be marked with the appropriate RHA designator. Device classes Q and V devices shall meet or exceed the electrical performance characteristics specified in table I herein after exposure to the specified irradiation levels specified in the absolute maximum ratings herein and the RHA marked device shall be marked in accordance with MIL-I-38535. A dash (-) indicates a non-RHA device.
  - 1.2.2 Device type. The device type shall identify the circuit function as follows:

Device type	Generic number	Circuit function
01	54BCT245	Octal bus tranceivers with three-state outputs

1.2.3 Device class designator. The device class designator shall be a single letter identifying the product assurance level as follows:

Device class	Device requirements documentation
М	Vendor self-certification to the requirements for non-JAN class B microcircuits in accordance with 1.2.1 of MIL-STD-883
B or S	Certification and qualification to MIL-M-38510
Q or V	Certification and qualification to MIL-I-38535

1.2.4 Case outlines. For device classes M, B, and S, case outlines shall meet the requirements in appendix C of MIL-M-38510 and as listed below. For device classes Q and V, case outlines shall meet the requirements of MIL-I-38535, appendix C of MIL-M-38510, and as listed below.

Outline letter	Case outline
R	D-8 (20-lead, 1.060" x .310" x .200"), dual-in-line package
S	F-9 (20-lead, .540" x .300" x .100"), flat package
2	C-2 (20-terminal, .358" x .358" x .100"), square chip carrier package

STANDARDIZED MILITARY DRAWING	SIZE <b>A</b>		5	5962-90514		
DEFENSE ELECTRONICS SUPPLY CENTER DAYTON, OHIO 45444		REVISION LEV	/EL	SHEET 2		

1.0.5							
1.2.5 Lead finish. The lead finish or MIL-I-38535 for classes Q and V. Finits packaging. The "X" designation is a considered acceptable and interchangeable	for use in	, v Speci	fications	MIL-M-38 t be mark s when le	3510 for sed on t ad fini	classes M, B, and S he microcircuit or shes A, B, and C is	
1.3 Absolute maximum ratings. 1/							
Supply voltage range $(V_{CC})$ DC input voltage range $(V_{IN})$ :  Including I/O ports Excluding I/O ports Voltage applied to any output in the low Input clamp current $(I_{IC})$ Storage temperature range Lead temperature (soldering, 10 se Thermal resistance, junction-to-ca Junction temperature $(T_{IC})$ Power dissipation $(P_D)$	he high she disable state	 tate ed sta 	te	-0.5 V -0.5 V -0.5 V -0.5 V 96 mA -30 mA -65°C t +300°C	dc to + dc to + dc to V dc to +  c + 150°(	5.5 V dc 7.0 V dc CC 5.5 V dc	
1.4 Recommended operating conditions.				•	-		
Supply voltage range (V <sub>CC</sub> ) Minimum high level input voltage (Maximum low level input voltage (V Maximum high level output current Al through A8 B1 through B8 Maximum low level output current (A1 through A8 B1 through B8	I <sup>OT</sup> ):  I <sup>I</sup> ) I <sup>I</sup>			2.0 V do 0.8 V do -3 mA -12 mA			
1.5 Logic testing for device class Q							
Fault coverage measurement of manu logic tests (MIL-STD-883, test met	facturing nod 5012)			XX perce	ent <u>3</u> /		
<ul> <li>Stresses above the absolute maximum rating may cause permanent damage to the device. Extended operation at the maximum levels may degrade performance and affect reliability.</li> <li>Must be able to withstand the additional PD due to the short circuit test, IOS. The PD number listed is based upon dc values.</li> <li>Values will be added when they become available.</li> </ul>							
STANDARDIZED	SIZE						
MILITARY DRAWING	Α				59	62-90514	
DEFENSE ELECTRONICS SUPPLY CENTER DAYTON, OHIO 45444			REVISION	LEVEL		SHEET	

# 2. APPLICABLE DOCUMENTS

2.1 Government specifications, standards, bulletin, and handbook. Unless otherwise specified, the following specifications, standards, bulletin, and handbook of the issue listed in that issue of the Department of Defense Index of Specifications and Standards specified in the solicitation, form a part of this drawing to the extent specified herein.

**SPECIFICATIONS** 

MILITARY

MI L-M-38510

MIL-I-38535

- Microcircuits, General Specification for. Integrated Circuits, Manufacturing, General Specification for.

STANDARDS

MILITARY

MIL-STD-480 MIL-STD-883

Configuration Control-Engineering Changes, Deviations and Waivers.

Test Methods and Procedures for Microelectronics.

BULLETIN

MILITARY

MIL-BUL-103

- List of Standardized Military Drawings (SMD's).

HANDBOOK

MILITARY

MI L-HUBK-780

- Military Drawings.

(Copies of the specifications, standards, bulletin, and handbook required by manufacturers in connection with specific acquisition functions should be obtained from the contracting activity or as directed by the contracting activity.)

2.2 Order of precedence. In the event of a conflict between the text of this drawing and the references cited herein, the text of this drawing shall take precedence.

### 3. REQUIREMENTS

- 3.1 Item requirements. The individual item requirements for device classes M shall be in accordance with 1.2.1 of MIL-STD-883, "Provisions for the use of MIL-STD-883 in conjunction with compliant non-JAN devices" and as specified herein. The individual item requirements for device classes B and S shall be in accordance with MIL-M-38510 and as specified herein. For device classes B and S a full electrical characterization table for each device type shall be included in this SMD. The individual item requirements for device classes Q and V shall be in accordance with MIL-I-38535 and as specified herein.
- 3.2 Design, construction, and physical dimensions. The design, construction, and physical dimensions shall be as specified in MIL-M-38510 for device classes M, B, and S and MIL-I-38535 for device classes Q and V and herein.
  - 3.2.1 Case outlines. The case outlines shall be as specified in accordance with 1.2.4 herein.

**STANDARDIZED** SIZE Α MILITARY DRAWING 5962-90514 **DEFENSE ELECTRONICS SUPPLY CENTER REVISION LEVEL** SHEET DAYTON, OHIO 45444

DESC FORM 193A

- 3.2.2 <u>Terminal connections</u>. The terminal connections shall be as specified on figure 1.
- 3.2.3 Truth table. The truth table shall be as specified on figure 2.
- 3.2.4 Logic diagram. The logic diagram shall be as specified on figure 3.
- 3.3 Electrical performance characteristics and postirradiation parameter limits. Unless otherwise specified herein, the electrical performance characteristics and postirradiation parameter limits are as specified in table I and shall apply over the full case operating temperature range.
- 3.4 Electrical test requirements. The electrical test requirements shall be the subgroups specified in table IIA. The electrical tests for each subgroup are defined in table I.
- $3.5\,$  Marking. The part shall be marked with the PIN listed in 1.2 herein. Marking for device class M shall be in accordance with MIL-STD-883 (see  $3.1\,$  herein). In addition, the manufacturer's PIN may also be marked as listed in MIL-BUL-103. Marking for device classes B and S shall be in accordance with MIL-M-38510. Marking for device classes Q and V shall be in accordance with MIL-I-38535.
- 3.5.1 Certification/compliance mark. The compliance mark for device class M shall be a "C" as required  $\overline{\text{in MIL-STD-883}}$  (see 3.1 herein). The certification mark for device classes B and S shall be a "J" or "JAN" as required in MIL-M-38510. The certification mark for device classes Q and V shall be a "QML" as required in MIL-I-38535.
- 3.6 Certificate of compliance. For device class M, a certificate of compliance shall be required, from a manufacturer in order to be listed as an approved source of supply in MIL-BUL-103 (see 6.7.3 herein). For device classes Q and V, a certificate of compliance shall be required from a QML-38535 listed manufacturer in order to supply to the requirements of this drawing (see 6.7.2 herein). The certificate of compliance submitted to DESC-ECS prior to listing as an approved source of supply for this drawing shall affirm that the manufacturer's product meets, for device class M the requirements of MIL-STD-883 (see 3.1 herein), or for device classes Q and V, the requirements of MIL-I-38535 and the requirements herein.
- 3.7 Certificate of conformance. A certificate of conformance as required for device class M in MIL-STD-883 (see 3.1 herein) or device classes B and S in MIL-M-38510 or for device classes Q and V in MIL-I-38535 shall be provided with each lot of microcircuits delivered to this drawing.
- 3.8 Notification of change for device class M. For device class M, notification to DESC-ECS of change of product (see 6.2 herein) involving devices acquired to this drawing is required for any change as defined in MIL-STD-480.
- 3.9 Verification and review for device class M. For device class M, DESC, DESC's agent and the acquiring activity retain the option to review the manufacturer's facility and applicable required documentation. Offshore documentation shall be made available onshore at the option of the reviewer.
- 3.10 Microcircuit group assignment for device classes M, B, and S. Device classes M, B, and S devices covered by this drawing shall be in microcircuit group number 126 (see MIL-M-38510, appendix
- 3.11 Serialization for device class S. All device class S devices shall be serialized in accordance with MIL-M-38510.
  - 4. QUALITY ASSURANCE PROVISIONS
- 4.1 Sampling and inspection. For device class M sampling and inspection procedures shall be in accordance with section 4 of MIL-M-38510 to the extent specified in MIL-STD-883 (see 3.1 herein). For device classes B and S, sampling and inspection procedures shall be in accordance with MIL-M-38510 and method 5005 of MIL-STD-883, except as modified herein. For device classes Q and V, sampling and inspection procedures shall be in accordance with MIL-I-38535.

STANDARDIZED MILITARY DRAWING	SIZE <b>A</b>				5962-90514		
DEFENSE ELECTRONICS SUPPLY CENTER DAYTON, OHIO 45444			REVISION LEVEL		SHEET	5	

DESC FORM 193A

١.

Test		  Symbol	ectrical performa  Condi -55°C < To	tions < +125°C ise specified	   Group A  subgroups		     Unit	
			l unless otherw	ise specified			Max	
High level output voltage	Any A	V <sub>OH</sub>	V <sub>CC</sub> = 4.5 V,   V <sub>IH</sub> = 2.0 V,   V <sub>IL</sub> = 0.8 V	I <sub>OH</sub> = -1 mA	1,2,3	2.5		٧
		 		$I_{OH} = -3 \text{ mA}$	 _!	2.4	 	
	Any B		 	$I_{OH} = -3 \text{ mA}$		   2.4 	]	
				I <sub>OH</sub> = -12 mA		   2.0 		
Low level output voltage	Any A	V <sub>OL</sub>	V <sub>CC</sub> = 4.5 V,   V <sub>IH</sub> = 2.0 V,   V <sub>IL</sub> = 0.8 V	I <sub>OL</sub> = 20 mA	1,2,3		0.50	
	Any B		V <sub>IL</sub> = 0.8 V	$I_{OL} = 48 \text{ mA}$	 		0.55	
Input clamp voltage		AIC	$V_{CC} = 4.5 \text{ V}, I_{II}$	N = -18 mA	1,2,3	 	-1.2	٧
High level input current $1/$	A and B	I IH1	V <sub>CC</sub> = 5.5 V	$ V_{IN}  = 5.5 V$	1,2,3		1.0	mA
	DIR and G	 			 		0.1	
	A and B	  I <sub>IH2</sub>	V <sub>CC</sub> = 5.5 V	V <sub>IN</sub> = 2.7 V	1,2,3		70	μ <b>A</b>
	  DIR and G   	] 	 	 	[		20	
STANDA MILITARY I		6	SIZE A			-90514	· · · · · · · · · · · · · · · · · · ·	

Test		  Symbol	Cond   -55°C < 1   unless other	litions C < +125°C wise specified	Group A	Lim	     Unit	
Low level input	  A and B	I IIIL	V <sub>CC</sub> = 5.5 V, V		1,2,3		Max    -0.65	mA
current <u>l</u> /	DIR and G		   	•••	     	<del> </del>	-1.2	tin.
Output current   Any A			V <sub>CC</sub> = 5.5 V,		1,2,3	-60	-150	mA
	  Any B 	! ! !				-100	-225	
Supply current <u>3</u> /		I CCH	V <sub>CC</sub> = 5.5 V	Outputs high	1,2,3		57	
		ICCL		  Outputs low 			90	
		l Iccz I		  Outputs disabled			15	
Functional tests			See 4.4.1b	4/	7,8			
Propagation delay time, in A or B to B or A		t <sub>PLH</sub>	V <sub>CC</sub> = 5.0 V C <sub>L</sub> = 50 pF R <sub>1</sub> = R <sub>2</sub> = 500Ω See figure 4		9	1.0	6.0	ns
			$V_{CC}$ = 4.5 V to 9 $C_L$ = 50 pF $R_1$ = $R_2$ = 500 $\Omega$ See figure 4	5.5 Y	10,11	1.0	7.2	
	   	t <sub>PHL</sub>	V <sub>CC</sub> = 5.0 V C <sub>L</sub> = 50 pF R <sub>1</sub> = R <sub>2</sub> = 500Ω See figure 4		9	1.5	6.6	
			V <sub>CC</sub> = 4.5 V to 5 C <sub>L</sub> = 50 pF R <sub>1</sub> = R <sub>2</sub> = 500Ω See figure 4	.5 V	10,11	1.5	7.6	
see footnotes at end	of table.					•		
STANDAF MILITARY D		<u> </u>	SIZE A		5000			<u></u>
MILLIMANT	,, 174441147	_4			5962-	90514		

Ţ	AbLE 1. Elect	rical performance characteristics	- Continue	1.		
Test	  Symbol	Conditions  -55°C < T <sub>C</sub> < +125°C  unless otherwise specified	Group A  subgroups	Lim	     Unit	
	i	i antess otherwise specified		Min	l   Max	! !
Output enable time, G to A, G to B	ltpZH 	V <sub>CC</sub> 5.0 V  C <sub>L</sub> = 50 pF  R <sub>1</sub> = R <sub>2</sub> = 500Ω  See figure 4	9	1.5	9.4	l I ns
	[	   V <sub>CC</sub> 4.5 V to 5.5 V  C <sub>L</sub> = 50 pF  R <sub>1</sub> = R <sub>2</sub> = 500Ω   See figure 4	10,11	1.5	   11.2   	
	t <sub>PZL</sub>	  V <sub>CC</sub> 5.0 V  C <sub>L</sub> = 50 pF  R <sub>I</sub> = R <sub>2</sub> = 500Ω  See figure 4		1.5	10.2	
		$V_{CC}$ 4.5 $V$ to 5.5 $V$ $U_{L}$ = 50 pF $R_{1}$ = $R_{2}$ = 500 $\Omega$ See figure 4	10,11	1.5	11.8	
Output disable time, G to A, G to B	It <sub>PHZ</sub> I	$V_{CC}$ 5.0 V $C_L$ = 50 pF $R_1$ = $R_2$ = 500 $\Omega$ See figure 4	9	1.5	8.3    	ns
		$V_{CC}$ 4.5 V to 5.5 V $C_L$ = 50 pF $R_1$ = $R_2$ = $500\Omega$ See figure 4	10,11	1.5	9.7	
	tpLZ	$V_{CC}$ 5.0 $V_{CL}$ = 50 pF $R_1$ = $R_2$ = 500 $\Omega$ See figure 4	9	1.5	1           	
		$V_{CC}$ 4.5 V to 5.5 V $C_L$ = 50 pF $R_1$ = $R_2$ = 500 $\Omega$ See figure 4	10,11	1.5	9.6	

For I/O ports, the parameters  $I_{IH2}$  and  $I_{IL}$  include the off-state output current. Not more than one output should be shorted at one time and the duration of the test condition shall not exceed 1 second.

3/  $I_{CCH}$  and are  $I_{CCL}$  is measured in the A to 8 mode.

4/ Functional tests shall be conducted at input test conditions of 0.4 V <  $V_{IL} \le 0.8$  V and 2.0 V  $\le V_{IH} \le 2.4$  V for  $V_{CC} = 4.5$  V and is repeated at  $V_{CC} = 5.5$  V.

STANDARDIZED MILITARY DRAWING	SIZE <b>A</b>		59	5962-90514		
DEFENSE ELECTRONICS SUPPLY CENTER DAYTON, OHIO 45444		REVISION LEVEL	,	SHEET		

  Device type	01						
  Case outlines	R, S, and 2						
Terminal number	Terminal symbol						
1	DIR A1 A2 A3 A4 A5 A6 A7 A8 GND B8 B7 B6 B5 B4 B3 B2 B1 G						

FIGURE 1. Terminal connections.

Enable     G	Direction control DIR	Operation
	L	B data to A bus I
L	H	A data to B bus I
H	X	Isolation

L = Low voltage level H = High voltage level X = Irrelevant

FIGURE 2. Truth table.

#### **STANDARDIZED** SIZE **MILITARY DRAWING** Α 5962-90514 DEFENSE ELECTRONICS SUPPLY CENTER DAYTON, OHIO 45444 **REVISION LEVEL** SHEET





FIGURE 3. Logic diagram.

**STANDARDIZED** SIZE Α **MILITARY DRAWING** 5962-90514 DEFENSE ELECTRONICS SUPPLY CENTER DAYTON, OHIO 45444 REVISION LEVEL SHEET 10

DESC FORM 193A SEP 87



 $C_L$  = 50 pF, includes probe and jig capacitance.  $R_L$  =  $R_1$  =  $R_2$  =  $500\,\Omega$ 

SWITCH POSITION TABLE


-	Test	S1
	tPLH tPHL tPZH tPZL tPHZ tPLZ	Open Open Open Closed Closed Closed

FIGURE 4. Switching waveforms and test circuit.

STANDARDIZED
MILITARY DRAWING
DEFENSE ELECTRONICS SUPPLY CENTER
DAYTON, OHIO 45444

SIZE
A
5962-90514

REVISION LEVEL
SHEET
11



### NOTES:

- 1. Output with internal conditions such that the output is low except when disabled by the output control.
- Output with internal conditions such that the output is high except when disabled by the output control.
- 3. All input pulses are supplied by the generators having the following characteristics: PRR  $\leq$  10 MHz,  $Z_0 = 50\Omega$ ,  $t_r \leq 2.5$  ns,  $t_f \leq 2.5$  ns. 4. The outputs are measured one at a time with one transition per measurement.

FIGURE 4. Switching waveforms and test circuit - Continued.

STANDARDIZED MILITARY DRAWING	SIZE <b>A</b>		5962-90514
DEFENSE ELECTRONICS SUPPLY CENTER DAYTON, OHIO 45444		REVISION LEVEL	SHEET

DESC FORM 193A SEP 87

- 4.2 Screening. For device class M, screening shall be in accordance with method 5004 of MIL-STD-883, and shall be conducted on all devices prior to quality conformance inspection. For device classes B and S, screening shall be in accordance with method 5004 of MIL-STD-883, and shall be conducted on all devices prior to qualification and quality conformance inspection. For device classes Q and Y, screening shall be in accordance with MIL-I-38535, and shall be conducted on all devices prior to qualification and technology conformance inspection. The following additional criteria shall apply.
  - a. Burn-in test, method 1015 of MIL-STD-883.
    - (1) Test condition A, B, C or D. For device class M the test circuit shall be submitted to DESC-ECS for review with the certificate of compliance. For device classes B and S, the test circuit shall be submitted to the qualifying activity. For device classes Q and V, the test circuit shall be submitted to DESC-ECS with the certificate of compliance and under the control of the device manufacturer's technical review board (TRB) in accordance with MIL-I-38535.
    - (2)  $T_A = +125^{\circ}C$ , minimum.
- b. Interim and final electrical test parameters shall be as specified in table IIA herein. For device class M, interim electrical parameter tests prior to burn-in are optional at the discretion of the manufacturer.
- 4.2.1 Additional screening for device class V. Additional screening for device class V beyond the requirements of device class Q shall be as specified in appendix B of MIL-I-38535 and as detailed in table IIB herein. These additional screens may be used to satisfy space system requirements and shall be reflected in the PIN.
  - 4.3 Qualification inspection.
- 4.3.1 Qualification inspection for device classes B and S. Qualification inspection for device classes B and S shall be in accordance with MIL-M-38510. Inspections to be performed shall be those specified in method 5005 of MIL-STD-883 and herein for groups A, B, C, D, and E inspections (see 4.4.1 through 4.4.5).
- 4.3.2 Qualification inspection for device classes Q and V. Qualification inspection for device classes Q and V shall be in accordance with MIL-I-38535. Inspections to be performed shall be those specified in MIL-I-38535 and herein for groups A, B, C, D, and E inspections (see 4.4.1 through 4.4.5).
- 4.4 Conformance inspection. Quality conformance inspection for device class M shall be in accordance with MIL-STD-883 (see 3.1 herein) and as specified herein. Quality conformance inspection for device classes B and S shall be in accordance with MIL-M-38510 and as specified herein. Inspections to be performed for device classes M, B, and S shall be those specified in method 5005 of MIL-STD-883 and herein for groups A, B, C, D, and E inspections (see 4.4.1 through 4.4.5). Technology conformance inspection for classes Q and V shall be in accordance with MIL-I-38535 including groups A, B, C, D, and E inspections and as specified herein.

STANDARDIZED MILITARY DRAWING	SIZE <b>A</b>		5962-90514	
DEFENSE ELECTRONICS SUPPLY CENTER DAYTON, OHIO 45444		REVISION LEVEL	SHEET 13	

- 4.4.1 Group A inspection.
  - Tests shall be as specified in table IIA herein.
  - b. For device class M, subgroups 7 and 8 tests shall be sufficient to verify the truth table. For device classes B and S, subgroups 7 and 8 tests shall be sufficient to verify the truth table as approved by the qualifying activity. For device classes Q and V, subgroups 7 and 8 shall include verifying the functionality of the device; these tests shall have been fault graded in accordance with MIL-STD-883, test method 5012 (see 1.5 herein).
  - c. Subgroups 4, 5, and 6 in table I, method 5005 of MIL-STD-883 shall be omitted.
- 4.4.2 Group B inspection. The group B inspection end-point electrical parameters shall be as specified in table TIA licroin.
  - 4.4.3 Group C inspection.
    - a. End-point electrical parameters shall be as specified in table IIA herein.
    - b. Steady-state life test conditions, method 1005 of MIL-STD-883:
      - (1) Test condition A, B, C or D. For device class M, the test circuit shall be submitted to DESC-ECS for review with the certificate of compliance. For device classes B and S, the test circuit shall be submitted to the qualifying activity. For device classes Q and V, the test circuit shall be submitted to DESC-ECS with the certificate of compliance and under the control of the device manufacturer's TRB in accordance with MIL-1-38535.
      - (2) TA = +125°C, minimum.
      - (3) Test duration: 1,000 hours, except as permitted by method 1005 of MIL-STD-883.
- 4.4.4 Group D inspection. For group D inspection, end-point electrical parameters shall be as specified in table IIA herein.
- 4.4.5 Group E inspection. Group E inspection is required only for parts intended to be marked as radiation hardness assured (see 3.5 herein). RHA levels for device classes B and S, shall be M, D, R, and H and for device class M shall be M and D. RHA quality conformance inspection sample tests shall be performed at the level specified in the acquisition document. RHA tests for device classes Q and Y, shall be performed in accordance with MLL-1-38535 and 1.2.1 herein.
  - a. RHA tests for device classes B and S for levels M, D, R, and H or for device class M for levels M and D shall be performed through each level to determine at what levels the devices meet the RHA requirements. These RHA tests shall be performed for initial qualification and after design or process changes which may affect the RHA performance of the device.
  - b. End-point electrical parameters shall be as specified in table IIA herein.
  - c. Prior to total dose irradiation, each selected sample shall be assembled in its qualified package. It shall pass the specified group A electrical parameters in table I for subgroups specified in table IIA herein.
  - d. For device classes M, B, and S, the devices shall be subjected to radiation hardness assured tests as specified in MIL-M-38510 for RHA level being tested, and meet the postirradiation end-point electrical parameter limits as defined in table I at T<sub>A</sub> = +25°C ±5 percent, after exposure.

# STANDARDIZED MILITARY DRAWING DEFENSE ELECTRONICS SUPPLY CENTER DAYTON, OHIO 45444 SIZE A 5962-90514 REVISION LEVEL SHEET

TABLE IIA. <u>Electrical test requirements</u> . 1/ 2/					
   Test requirements	   (per met	Subgroups hod 5005,t	Subgroups (per MIL-I-38535, table III)		
	Device class M	Device class B	Device class S	   Device   class   Q	Device     class   V
Interim electrical parameters (see 4.2)		1	1	1	1 1
Final electrical parameters (see 4.2)	  1*,2,3,7,  8,9,10,11	  1*,2,3,7,  8,9,10,11	  1*,2,3,7,  8,9,10,11	1*,2,3,7, 8,9,10,11	  1*,2,3,7,   8,9,10,11
Group A test requirements (see 4.4)	1,2,3,7,	   1.2.3.7.	11.2.3.7	1237	
Group B end-point electrical parameters (see 4.4)	   		1,2,3, 9,10,11		1,2,3,   9,10,11
Group C end-point electrical parameters (see 4.4)	1,2,3	1,2,3		1,2,3	
Group D end-point electrical parameters (see 4.4)	1,2,3	1,2,3	1,2,3	1,2,3	1,2,3
Group E end-point electrical parameters (see 4.4)	1,7,9	1,7,9	1,7,9	1,7,9	1,7,9

- $\underline{1}/$  Blank spaces indicate tests are not applicable.  $\underline{\overline{2}}/$  \* indicates PDA applies to subgroup 1.
- e. Prior to and during total dose irradiation testing, the devices shall be biased to establish a worst case condition as specified in the radiation exposure circuit.
  - (1) Inputs tested high,  $V_{CC}$  = volts dc,  $R_{CC}$  =  $\Omega$  +5%,  $V_{IN}$  = volts dc,  $R_{IN}$  =  $\Omega$  +20%, and all outputs are open. (Values will be added when they become available.)
  - (2) Inputs tested low V<sub>CC</sub> = volts dc, R<sub>CC</sub> =  $\Omega$  +5%, V<sub>IN</sub> = 0.0 V dc, and all outputs are open. (Values will be added when they become available.)
- f. For device classes M, B, and S, subgroups 1 and 2 in table V, method 5005 of MIL-STD-883 shall be tested as appropriate for device construction.
- g. When specified in the purchase order or contract, a copy of the RHA delta limits shall be supplied.

STANDARDIZED MILITARY DRAWING	SIZE A		5962-90514	· <u>.</u>
DEFENSE ELECTRONICS SUPPLY CENTER DAYTON, OHIO 45444		REVISION LEVEL	SHEET 15	

TADI E TID						•
INDUE IIB.	Additional	screening i	for	davica	clace V	
			, , ,	ue vice	CIASS V.	

Test	MIL-STD-883, test method	Lot requirement
Particle impact noise detection	2020	100%
Internal visual	2010, condition A or   approved alternate	100%
Nondestructive   bond pull	2023 or approved alternate	100%
  Reverse bias burn-in 	1015	100%
Burn-in   	1015, total of 240 hours   at +125°C	100%
  Radiographic 	2012	100%

- 5. PACKAGING
- 5.1 Packaging requirements. The requirements for packaging shall be in accordance with MIL-M-38510 for device classes M, B, and S and MIL-I-38535 for device classes Q and V.
  - 6. NOTES
- 6.1 Intended use. Microcircuits conforming to this drawing are intended for use for Government microcircuit applications (original equipment), design applications, and logistics purposes.
- 6.1.1 Replaceability. Microcircuits covered by this drawing will replace the same generic device covered by a contractor-prepared specification or drawing.
- 6.1.2 Substitutability. Device classes B and Q devices will replace device class M devices.
- 6.2 Configuration control of SMD's. All proposed changes to existing SMD's will be coordinated with the users of record for the individual documents. This coordination will be accomplished in accordance with MIL-STD-481 using DD Form 1693, Engineering Change Proposal (Short Form).
- 6.3 Record of users. Military and industrial users shall inform Defense Electronics Supply Center when a system application requires configuration control and which SMD's are applicable to that system. DESC will maintain a record of users and this list will be used for coordination and distribution of changes to the drawings. Users of drawings covering microelectronic devices (FSC 5962) should contact DESC-ECS, telephone (513) 296-6022.
- 6.4 Comments. Comments on this drawing should be directed to DESC-ECS, Dayton, Ohio 45444, or telephone (513) 296-5375.

STANDARDIZED MILITARY DRAWING	SIZE A		5962-90514		
DEFENSE ELECTRONICS SUPPLY CENTER DAYTON, OHIO 45444		REVISION LEVEL		SHEET	
DESC FORM 193A SEP 87	<u> </u>		± U. S. GOVERNME	16 NT PRINTING OFFICE: 1989—74	19-033

b.5 Symbols, definitions, and functional descriptions.

6.6 One part - one part number system. The one part - one part number system described below has been developed to allow for transitions between identical generic devices covered by the four major microcircuit requirements documents (MIL-M-38510, MIL-H-38534, MIL-I-38535, and 1.2.1 of MIL-STD-883) without the necessity for the generation of unique PIN. The four military requirements documents represent different class levels, and previously when a device manufacturer upgraded military product from one class level to another, the benefits of the upgraded product were unavailable to the Original Equipment Manufacturer (OEM), that was contractually locked into the original unique PIN. By establishing a one part number system covering all four documents, the OEM can acquire to the highest class level available for a given generic device to meet system needs without modifying the original contract parts selection criteria.

Military documentation format	Example PIN under new system	Manufacturing source listing	Document listing
New M1L-M-38510 Military Detail Specifications (in the SMD format)	5962-XXXXXZZ(B or S)YY	QPL-38510 (Part 1 or 2)	MIL-BUL-103
New MIL-H-38534 Standardized Military Drawings	5962-XXXXXZZ(H or K)YY	QML -38534	MIL-BUL-103
New MIL-I-38535 Standardized Military Drawings	5962-XXXXXZZ(Q or V)YY	QML-38535	MIL-BUL-103
New 1.2.1 of MIL-STD-883 Standardized Military Drawings	5962-XXXXXZZ(M)YY	MIL-BUL-103	MIL-BUL-103

# 6.7 Sources of supply.

- 6.7.1 Sources of supply for device classes B and S. Sources of supply for device classes B and S are listed in QPL-38510.
- 6.7.2 Sources of supply for device classes Q and V. Sources of supply for device classes Q and V are listed in QML-38535. The vendors listed in QML-38535 have submitted a certificate of compliance (see 3.6 herein) to DESC-ECS and have agreed to this drawing.
- 6.7.3 Approved sources of supply for device class M. Approved sources of supply for class M are listed in MIL-BUL-103. The vendors listed in MIL-BUL-103 have agreed to this drawing and a certificate of compliance (see 3.6 herein) has been submitted to and accepted by DESC-ECS.

# STANDARDIZED MILITARY DRAWING DEFENSE ELECTRONICS SUPPLY CENTER DAYTON, OHIO 45444 SIZE A 5962-90514 REVISION LEVEL SHEET

### STANDARDIZED MILITARY DRAWING SOURCE APPROVAL BULLETIN

DATE: 21 SEP 90

An approved source of supply for SMD 5962-90514 is listed below for immediate acquisition only and shall be added to MIL-BUL-103 during the next revision. MIL-BUL-103 will be revised to include the addition or deletion of sources. The vendor listed below has agreed to this drawing and a certificate of compliance has been submitted to and accepted by DESC-ECS. This bulletin is superseded by the next dated revision of MIL-BUL-103.

Standardized military drawing PIN	Vendor     CAGE   number	Vendor similar PIN <u>1</u> /
5962-9051401MRX	01295	SNJ54BCT245J
5962-9051401MSX	01295	SNJ54BCT245W
5962-9051401M2X	01295	SNJ54BCT245FK

 $\frac{1}{}$  Caution. Do not use this number for item acquisition. Items acquired to this number may not satisfy the performance requirements of this drawing.

Vendor CAGE number

01295

Vendor name and address

Texas Instruments, Incorporated 13500 North Central Expressway P.O. Box 655303 Dallas, TX 75265 Point of contact: I-20 at FM 1788

Midland, TX 79711-0448

The information contained herein is disseminated for convenience only and the Government assumes no liability whatsoever for any inaccuracies in this information bulletin.